



BFRC Air Permeability Test method following the principles of BS EN 1026:2000 Windows and Doors

Client:	FABCO Sanctuary Ltd
Project:	Air Permeability testing on FABCO SMW side hung steel Window
Project reference:	W13129-2
Issue date:	04/06/2013
Prepared By:	
Test dates:	21/5/2013
Items tested:	1

Build Check Ltd
Montrose House
Lancaster Road
Cressex Business Park
High Wycombe
Bucks
HP12 3PY

Tel: 01494 452713
Fax: 08702 101013
E-mail: info@buildcheck.co.uk



This document is confidential and remains the property of Build Check Ltd
This test falls outside the scope of Build Check Ltd UKAS accreditation

1.0 Summary

The BFRC Air Permeability at 50Pa was commissioned by Fabco Sanctuary Ltd Unit 1Hobbs New Barn, Climping, Littlehampton, West Sussex BN17 5TF and was performed in accordance with the following method:

BFRC Energy Rating Guidelines
Air Permeability tests following the principles in BS EN 1026:2000.

This report only relates to the actual sample tested.

2.0 Test Specimen

The specimen was received on 30th April 2013.

Sample type: SMW Side Hung Opening / Fixed
Brand/range name: Fabco SMW

Finish: Black
Construction: Frame: Steel
Sash: Steel

Glazing: Double glazed, 4-8-4 mm sealed units
Dimensions: Outer frame (w x h x t): 1210 x 1460 x 26 mm
Opening light (w x h x t): 560 x 1140 x 26 mm

3.0 Test Details

Test Date: 21st May 2013

Test conditions in accordance with standard.

4.0 Results

Average between positive and negative pressure						
Air Pressure (Pa)	Positive pressure		Negative pressure		Mean	
	Net permeability per m ² area (m ³ /h·m ²)	Net permeability per m opening length (m ³ /h·m)	Net permeability per m ² area (m ³ /h·m ²)	Net permeability per m opening length (m ³ /h·m)	Per m ² area (m ³ /h·m)	Per m opening length (m ³ /h·m)
50	0.0	0.0	3.01	1.35	1.47	0.66

5.0 Test Specimen Photograph

